

# POWER TEX ASSOCIATES.

Generators, Automation, Solar systems & Mechanical Fabrication

#### Attn.Mr.Muhammad

Ref/10kw/CH/23

## **QUOTATION**

**Johar Town Lahore** 

#### QUOTATION FOR 10.0 KW ONGRID WITH 5.6KW PANELS SOLAR SYSTEM

QUOTE NO-	DATE	CUSTOMER CODE.	PAYMENT TERMS
10KW/23	7/11/2023	СН	CASH/CHEQUE.

#### N.T.N # 1504616-8

S#	DESCRIPTION	QTY.	UNIT.	TOTAL
			Net	NET
1	PV Panels of 555/550 P-type each panel A+ make Longi/jinko Tier-1 Mono Perc	10	36,630	366,300.00
2	Solar Inverter 10KW Ongrid Three phase Smart Starting Inverter Ongrid.	1	275,000	275,000.00
4	Solar Structure L2 14/16 SWG	5	5,700	28,500.00
5	DC Cables 1000 vdc estimated ,6sq mm. (ft) 2 Coil G.M, Fast cables	320	150	48,000.00
6	AC Cables 8 sq mm, single core for inverter to load/meter DB (ft)	40	250	10,000.00
7	DB Panel with Brackers,AC/DC and allied mate including wall panel 16SWG powder coated	1	25,000	25,000.00
8	Earthing cable yellow/Green 10 sq mm1-C	job	15,000	15,000.00
9	Earthing ,Boring upto water level first or 50-70 feet with copper Rod, 5 ft dia 3/4 includes 10 sq mm bare copper rope nut bolts etc for AC and DC system	2	25,000	50,000.00
				-
Sub.Total				817,800.00

Continue

NETMETERING DETAILS						
	Netmetering system					
11	Providing net metering of system as per rules regarding for netmetering Govt Fee and third party testing commissioning of the net metering and apporvals from concerns depend on the time with Discos/Lesco approx 1 to 2 months	1	120,000	120,000.00		
Transportation of Materials from works to Site						
11	Materials Transportation To Site with loading un loading of materials.	Job	10,000	10,000.00		
Installation Testing Commissioning and Design						
12	Installation of PV Panels, Mounting, structure PV Panel Cables pulling, DC Cables within the PV modules and to invertor installation of invertor, MCCBs, Distribution Panels AC/DC cables from invertor to DB, complete in all respects.	JOB	40,000	40,000.00		

|--|

Note: Quotation is only valid for next 5 days due to uncertain prices in market

### Terms & conditions.

Payment:	80% advance at the time of confirm work order./ 10% at the time of Delivery.	
	10% Balance after completion of our jobs.	
	After 15 days if jobs delays or extra visits it will cost as per site.	
Extra job:	Any Extra Job will be charge as per site requirement.	
Warranty:	10 years warranty for Solar Panel and 25 years performance of panel life.	
	02 year warranty for Invertor . As per Manufecturer	

#### NOTE:

1.During Installation Customer is responsible to provide excess installation team as per requirement of the job and provide permission from owner of house for civil and welding works on site 2.We will provide our technical assistance during office hours 10.AM to 6.00PM only on working days.

Thanking You Best regards.

Power Tex Associates. Muhammad Ayaz Khan 923454005432

NTN -1504616-8 GST -03-05-8537-007-028- PRA- PNTN-P1504616-8

Thank You For Power lev Facilities and Services

Best Regards

Muhammadl Aydz Khan

(Manager Marketing)

Project Engineer Engr. Ali Raza 923078339085

Seving the Power Industry since 1999.

 $LG26\text{-}Eden\ Tower\ Main\ Boulevard\ Gulberg\ Lahore.\ .Email,\ powertex@hotmail.com$